







**CLADE**

**OAK 100kW HEAT PUMP //**

Sept 22 //



## DIMENSIONAL INFORMATION //





## TECHNICAL INFORMATION //

Clade Oak ASHP		Oak -100Kw ASHP	
Nominal conditions: Water side		flow 45c to 85c Return temperature <35°C	
Nominal conditions: CO <sub>2</sub> side		Ambient air temperature +3°C (85% RH) and -9°C evaporation	
Compressor Manufacturer		Dorin	
Compressor Heating Qty	Pcs.	1	
Compressor Paralell Qty	Pcs.	2	
Compressor Power @ Design total	kW	40.4	
Evaporator fans Power at design	kW	3.6	
Total	kW	44	
Heat Pump Design Run Amps DRA	A	80	
Ancillary Controls Amps	A	4	
Total Amps		84	
Variable speed drive (VSD)	Pcs.	1	
Refrigerant charge (CO <sub>2</sub> )	kg	90	
Electrical supply	-	3~ 400V 50 HZ	
Housing Weight (empty)	kg	1,270	
Housing Weight (operational)	kg	1,315	
Load Cell A Weight (empty)	kg	657	
Load Cell A Weight (operational)	kg	702	
Load Cell B Weight (empty)	kg	N/A	
Load Cell B Weight (operational)	kg	N/A	
Sound Power compressor only	dB(A)	59	
Connections waterside flow	DN	42mm Copper	
Connections waterside Return	DN	42mm Copper	
Connections waterside Pressure Rating	PN	10	
Waterside Burst Disk	PN	10	
Communication protocol	-	MODBUS/BACNET	
IP-Class	-	IP54	
Evaporators Type		V Block	
No. evaporators	Pcs.	4	
Fin Material	-	AL/MG	
Defrost Type	-	Cool Gas CO <sub>2</sub>	
Defrost medium	-	CO <sub>2</sub>	
Defrost design/condition	-	> +6c ambient Off Cycle / < +6c ambient Cool Gas	
Fan regulation	-	0-10v	
Colour	-	BS48 – 000A05 TEXTURED GREY	





## HEAT PUMP PERFORMANCE //

Noise Performance Characteristics					
Model name	Nameplate output (kW)	Output Temp (°C)	Noise Data db(A)		
			Sound Power	Sound Pressure @ 1m	Sound Pressure @ 10m
Oak 100Kw	100	65	87	59	47
		70	87	59	47
		75	88	60	48
		80	88	60	48

Clade Heat Pump Performance Characteristics																													
Model name	Nameplate output (kW)	Output Temp (°C)	Return Temp (°C)	SCOP	SPF	-10°C External			-5°C External			0°C External			5°C External			10°C External			15°C External			20°C External			25°C External		
						QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)
Oak 100kW	100	55	35	2.8	2.9	80	39	2.06	100	44	2.29	110	43	2.57	120	42	2.86	120	38	3.13	120	35	3.39	120	33	3.63	120	30	3.95
		60	35	2.8	2.9	80	39	2.06	100	44	2.29	110	43	2.57	120	42	2.86	120	38	3.13	120	35	3.39	120	33	3.63	120	30	3.95
		65	35	2.8	2.9	80	39	2.06	100	44	2.29	110	43	2.57	120	42	2.86	120	38	3.13	120	35	3.39	120	33	3.63	120	30	3.95
		70	35	2.8	2.9	80	40	2.01	100	45	2.2	110	44	2.5	120	43	2.8	120	39	3.05	120	36	3.3	120	34	3.55	120	31	3.9
		75	35	2.8	2.9	80	40	2	100	45	2.2	110	44	2.5	120	43	2.8	120	39	3.05	120	36	3.3	120	34	3.55	120	31	3.9
		80	35	2.8	2.9	80	40	2	100	45	2.2	110	44	2.5	120	43	2.8	120	39	3.05	120	36	3.3	120	34	3.55	120	31	3.9

Clade Heat Pump Performance Characteristics																													
Model name	Nameplate output (kW)	Output Temp (°C)	Return Temp (°C)	SCOP	SPF	-10°C External			-5°C External			0°C External			5°C External			10°C External			15°C External			20°C External			25°C External		
						QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)	QH (kW)	PI (kW)	COPH (-)
Oak 100kW	100	55	30	3	3.1	80	36	2.22	100	40	2.48	110	40	2.78	120	39	3.09	120	35	3.39	120	33	3.66	120	31	3.93	120	28	4.27
		60	30	3	3.1	80	36	2.22	100	40	2.48	110	40	2.78	120	39	3.09	120	35	3.39	120	33	3.66	120	31	3.93	120	28	4.27
		65	30	3	3.1	80	36	2.22	100	40	2.48	110	40	2.78	120	39	3.09	120	35	3.39	120	33	3.66	120	31	3.93	120	28	4.27
		70	30	3	3.1	80	37	2.15	100	42	2.4	110	41	2.7	120	40	3	120	36	3.3	120	33	3.6	120	31	3.85	120	29	4.2
		75	30	3	3.1	80	37	2.15	100	42	2.4	110	41	2.7	120	40	3	120	36	3.3	120	33	3.6	120	31	3.85	120	29	4.2
		80	30	3	3.1	80	37	2.15	100	42	2.4	110	41	2.7	120	40	3	120	36	3.3	120	33	3.6	120	31	3.85	120	29	4.2



## BUILDING CONNECTIONS //

### POWER

3 phase.

Connection box mounted in position shown.

Isolation at control panel only.

Installer to provide local isolator external to heat pump.

### HEATING

Supplied with primary pump with 14m spare head.

Flow and return located in position shown.

PN 10 Flanged steel connections with butterfly valve.

### CONDENSATE

Condensate from the evaporator will drain centrally from the base of the unit.


It is recommended that a gully be installed below the heat pump and lead to a soak away.

### CONTROLS

The heat pump has self contained controls that manage its operation and the primary pump.

#### Alarms

- ❖ Hardwired shut down signal for fire alarm
- ❖ CO<sub>2</sub> detection
- ❖ Other fault
- ❖ High return water temperature.




## SYSTEM DESIGN

Here are our recommendations for good system design, however each building and application is different and so the system should be designed to meet the specific needs of the building.

The designer should aim to minimise the return water temperature to the heat pump in order to generate the highest COP possible.

Clade offers engineering support if required.

- ❖ Series arrangement of heat load by temperature with the lowest last
- ❖ Proper sizing of terminal units for high DT
- ❖ High quality two port control on terminal units to prevent high temperature bypass
- ❖ VSD pumping controlled on temperature at the index point
- ❖ Zero bypass on the system
- ❖ Proper commissioning of systems
- ❖ Data and analytics for continuous improvement
- ❖ Primary control on the return water temperature
- ❖ Thermal store to even out temperature variations





# LEEDS MANUFACTURING CENTRE //



- UK based
- 35 years of engineering experience
- Leeds manufacturing division
- Committed to sustainable business and sustainable products
- Investing in people, diversity & inclusion
- Non leveraged, owner operated



ACCREDITATIONS  
 ISO 9001:2015  
 ISO 14001:2015  
 OHSAS ISO 18001:2007



CERTIFICATIONS  
 Altius Assured Vendor Award  
 Altius ODM Vendor Award  
 CHAS  
 Sales Contractor



THANK YOU //

[www.clade-es.com](http://www.clade-es.com)

[Sales@clade-es.com](mailto:Sales@clade-es.com)

[Aftersales@clade-es.com](mailto:Aftersales@clade-es.com)

Head Office & Registered Office //  
Bristol & Bath Science Park,  
Dirac Crescent, Emersons Green,  
BRISTOL BS16 7FR

The Technology Centre //  
Unit R3 Gildersome Spur Industrial Estate,  
Stone Pits Lane, Morley,  
LEEDS LS27 7JZ

